

Wastewater treatment for tank refurbishment

Construction measure: Ludwigshafen @ BASF (DE) 04/2021

- Removal of leaded coating
- Construction company: Lobbe Industrial Service
- 2x surface blaster (2.500 bar, 40 l/min)
- 369m³ treated wastewater (→ internal sewage plant) resulting in 3m³ dewatered sludge (→ big bag for disposal)

